

Faster, simpler floors

ENGINEERED WOOD

BCI[®] Joists & VERSA-LAM[®] beams

NEW



OLD



Solid Timber

Versus

Simple Framing System by Boise Cascade

60	joists	31
52	bolts and washers	0
7	hangers	5
4	restraint straps	4
0	partition noggins	12
44	mid span blocking	0
60m2	insulation (sound)	0
1570	material weight (kg)	630
every piece by hand	site cutting	supplied precision cut and easy to trim if needed
1.5 - 2 days	installation time	Approx 4 hours
notching/drilling	pipework runs	easy to route through web
notching/drilling	electrical runs	knock-out holes in web
will shrink and may squeak	floor structure	flat and squeak free



Boise Cascade
Engineered Wood Products



competitive price, premium value